
Wednesday, 25/06/2008 9:58:19 AM

User\$ Jean-Luc Menard **Process Sheet** Customer : CU-DAR001 Dart Helicopters Services **Drawing Name** : LOCKING SLEEVE Job Number : 40023 **Estimate Number** : 12062 Part Number : PB6743001137 P.O. Number : 25/06/2008 - B6743001 PAGE35 This Issue S.O. No. : **Drawing Number** : NC : N/A Prsht Rev. Project Number : 11 : MACHINED PARTS : B1 First Issue **Drawing Revision** : 40023 Material **Previous Run** Each **Due Date** : 02/07/2008 Qtv: 10 Um: Written By Checked & Approved By Comment : Est. A 05.08.29 Est Rev:B Now on Doosan Lathe 08-06-25 JLM Verified By:EC **Additional Product** Job Number: **Machine Or Operation:** Description: Seq. #: 1.0 M6061T6T1000W065 6061T6 TUBE Comment: Qty.: 0.1860 f(s)/Unit Total: 1.8596 f(s) 6061T6 TUBE Turn as per Dwg B67-43001 Dwg Rev: Material: 6061-T6 (QQ-A-200/8 or QQ-A-225/8) Ø1.00 x .065" wall tubing (M6061T6T1.000W.065) Identify for B67-43001-137 Batch: 14(08 386 Deburr 2.0 DOOSAN LATHE Comment: DOOSAN LATHE Rev: 181 & Dwg B67-43001-1Rev: 131 1- Turn as per Folio FA 2-Deburr per dwg B67-43001-1 3.0 QC2 Comment: INSPECT PARTS AS THEY COME OFF MACHINE SECOND CHECK 4.0 QC8 Comment: SECOND CHECK

Wednesday, 25/06/2008 9:58:19 AM Jean-Luc Menard **Process Sheet** Customer: CU-DAR001 Dart Helicopters Services Drawing Name: LOCKING SLEEVE Job Number: 40023 Part Number: PB6743001137 Job Number: Machine Or Operation: Seq. #: Description: 5.0 HAND FINISHING1 HAND FINISHING RESOURCE #1 Comment: HAND FINISHING RESOURCE #1 Chemical Conversion Coat as per QSI 005 4.1 6.0 POWDER COATING POWDER COATING m102316 Comment: POWDER COATING Powder Coat Green Sandtex (Ref: 4.3.5.8) as per QSI 005 4.3 Mask inside sleeve START TIME: **OVEN TEMPERATURE FINISH TIME:** 7.0 QC3 POWDER COAT/CHEMICAL CONVERSI Comment: INSPECT POWDER COAT/CHEMICAL CONVERSION 8.0 PACKAGING RESOURCE #1 Comment: PACKAGING RESOURCE #1 Identify and Stock Location: 1/0 9.0 QC21 FINAL INSPECTION/WO RELEASE Comment: FINAL INSPECTION/W/O RELEASE Job Completion



-DART-AEROSPACE LTD	Work Order: 40023
	Bart Name   B/ 1 1/200   /2
Description: LOCKING SLEEVE	Part Number:
Inspection Dwg: Rev:	Page 1 of 1

Pg 35

## FIRST ARTICLE INSPECTION CHECKLIST

X First Article Prototype

Drawing		Actual			Method of		
Dimension	Tolerance	Dimension	Accept	Reject	Inspection	Comments	
.885	+-005	,887					
-25	4030	-35					
2,08	+/030	. 077					
1015	+/010	.017					
1,08 ,018 2,00	1030	2008					
			<u>.</u> , ., ., .				
				,	· · · · · · · · · · · · · · · · · · ·		
						<u> </u>	

Meası	ured by:	la ,	Audited by: 88	Prototype Approval:	
<del></del>	Date:	08/06/09	Date: 08/06/29	Date:	MIN
					<del></del>
Rev	Date	Change		Revised by	Approved
Λ		Now Issue		K.I/.II M	1

